

Highways Department	Contract No. :
Resurfacing Works	
Contingency Plan	
<p>(1) If the planing machine breaks down, the stand-by machine stationed at _____ plant / _____ / _____ should be delivered to the site immediately. (within _____ minutes) [Note : When the stand-by machine arrives on site, the cold milling area should be re-assessed. <u>The cold milling should be stopped if it exceeds the time limit for _____.</u>]</p> <p>(2) If the <u>paver</u> or <u>road roller</u> breaks down, all cold milling should be stopped at once. Estimate the area that could be laid with bituminous material with the remaining time available according to Resurfacing Work Planning and Record Sheet (Appendix A Sheet 5 of 5). The stand-by machine should be delivered to the site from the plant at once. (within _____ minutes)</p> <p>(3) If serious failure occurs at the <u>supply of bituminous materials</u>, the back-up bituminous material supplier should be notified for the immediate supply of bituminous materials. If it fails to supply sufficient materials, the appropriate stand-by materials should be used to lay on the cold milled area. If the materials are inadequate, <u>cold instant pot hole filling material or temporary decking by steel plates</u> should be used instead. <u>Double white lines</u> should be put on the areas of uneven joints and uneven vertical lines. The road sign reminding the drivers of the uneven road surface should be provided and the duty person-in-charge of the HyD should be notified.</p> <p>(4) If the road cannot be opened before _____, the duty person-in-charge of the HyD (the regional Engineer or Inspector of Works) should be consulted to decide whether the <u>Transport Department First Contact Point (TDFCP) and Police traffic console</u> should be notified for the arrangement of appropriate contingency measures.</p> <p>(5) Other road closure teams should be immediately deployed to the site to help clear the road closure facilities when necessary.</p> <p>(6) In case of emergency, other unnecessary works such as the provision of road marking, cateyes and road studs should be stopped temporarily so as to open the traffic lane as soon as possible.</p>	