說明 NOTES

此圖根據第 SILE-G09號《修改1》圖則制訂，分別以橙色、淺藍色和粉紅色標明將暫時封閉的部分警校道、香葉道和南朗山道路段。

THIS DRAWING IS PREPARED BASED ON DRAWING NO. SILE-G09 (REVISION 1) AND IS INTENDED TO SHOW THE TEMPORARY PARTIAL CLOSURE OF SECTIONS OF POLICE SCHOOL ROAD, HEUNG YIP ROAD AND NAM LONG SHAN ROAD (HIGHLIGHTED IN ORANGE, LIGHT BLUE AND PINK RESPECTIVELY).

業興街 YIP HING STREET

業勤街 YIP KAN STREET

業發街 YIP FAT STREET

黃竹坑道 WONG CHUK HANG ROAD

塘邊徑 TONG BIN LANE

香葉道 HEUNG YIP ROAD

南朗山道 NAM LONG SHAN ROAD

惠福道 WELFARE ROAD

深灣道 SHUM WAN ROAD

警校道 POLICE SCHOOL ROAD

修訂以主水平基準為依據之擬建路軌大約水平(米)
PROPOSED APPROXIMATE TRACK LEVEL IN m P.D. AMENDED
A26

在工程進行中及完工後將會保留、改道或修改的現有道路及行人徑
EXISTING ROADS AND FOOTPATHS TO BE MAINTAINED, DIVERTED OR MODIFIED DURING AND AFTER CONSTRUCTION

現有的神龕將會拆卸
EXISTING SHRINE TO BE DEMOLISHED

在工程進行中將會修改或封閉南朗山道休憩處並於完工後重置
NAM LONG SHAN ROAD SITTING-OUT AREA TO BE MODIFIED OR CLOSED DURING CONSTRUCTION AND REPROVISIONED AFTER CONSTRUCTION

擬建的公共運輸交匯處的大約位置
APPROXIMATE LOCATION OF PROPOSED PUBLIC TRANSPORT INTERCHANGE

修訂擬建在黃竹坑的鐵路車站的布局
LAYOUT OF PROPOSED RAILWAY STATION AT WONG CHUK HANG AMENDED
A25

香葉道 HEUNG YIP ROAD
擬建的公共運輸交匯處 PROPOSED PUBLIC TRANSPORT INTERCHANGE
月台 PLATFORM
大堂 CONCOURSE
地面水平 GROUND LEVEL
擬建的箱形暗渠 PROPOSED BOX CULVERTS
A25 切面圖 不按比例 SECTION S NOT TO SCALE

修訂以主水平基準為依據之擬建路軌大約水平(米)
PROPOSED APPROXIMATE TRACK LEVEL IN m P.D. AMENDED
A26

修訂擬建的鐵路高架橋的布局及方案界線
LAYOUT OF PROPOSED RAILWAY VIADUCT AND BOUNDARY OF THE SCHEME AMENDED

在工程進行中及完工後將會保留、改道或修改的現有道路及行人徑及修訂方案界線
EXISTING ROADS AND FOOTPATHS TO BE MAINTAINED, DIVERTED OR MODIFIED DURING AND AFTER CONSTRUCTION AND BOUNDARY OF THE SCHEME AMENDED
A29

擬建在黃竹坑的鐵路車站的大約位置
APPROXIMATE LOCATION OF PROPOSED RAILWAY STATION AT WONG CHUK HANG

修訂擬建的升降機、樓梯及行人天橋的布局
LAYOUT OF PROPOSED LIFTS, STAIRS AND FOOTBRIDGE AMENDED
A33

擬建的車站入口的大約位置
APPROXIMATE LOCATION OF PROPOSED STATION ENTRANCES

擬建的箱形暗渠
PROPOSED BOX CULVERTS

南朗山道熟食市場的現有建築物將會修改
EXISTING BUILDING OF NAM LONG SHAN ROAD COOKED FOOD MARKET TO BE MODIFIED

大王爺廟將會保留
TAI WONG YE TEMPLE TO BE MAINTAINED

擬建的箱形暗渠
PROPOSED BOX CULVERTS

擬增建的緊急救援通道的大約位置
APPROXIMATE LOCATION OF PROPOSED ADDED EMERGENCY ACCESS
A31

建議的臨時施工區
PROPOSED TEMPORARY WORKS AREA

擬增建的緊急車輛通道的大約位置
APPROXIMATE LOCATION OF PROPOSED ADDED EMERGENCY VEHICULAR ACCESS
A9

在工程進行中將會修改或封閉南朗山道兒童遊樂場並於完工後重置
NAM LONG SHAN ROAD CHILDREN'S PLAYGROUND TO BE MODIFIED OR CLOSED DURING CONSTRUCTION AND REPROVISIONED AFTER CONSTRUCTION

擬建的水務設施、渠務設施、其他公用事業設施及鐵路營運相關的其他設施的大約位置
APPROXIMATE LOCATION OF PROPOSED WATERWORKS, DRAINAGE WORKS, OTHER UTILITY FACILITIES AND OTHER FACILITIES ANCILLARY TO THE OPERATION OF THE RAILWAY

修訂擬建的鐵路高架橋的布局
LAYOUT OF PROPOSED RAILWAY VIADUCT AMENDED
A22

在工程進行中及完工後將會修改或封閉部分現有位於天台的休憩處
PART OF EXISTING SITTING-OUT AREA AT ROOF TOP TO BE MODIFIED OR CLOSED DURING AND AFTER CONSTRUCTION

包玉剛游泳池 Pao Yue-kong Swimming Pool

在工程進行中及完工後將會保留、改道或修改的現有道路及行人徑
EXISTING ROADS AND FOOTPATHS TO BE MAINTAINED, DIVERTED OR MODIFIED DURING AND AFTER CONSTRUCTION
A35

連接觀海徑及擬建在黃竹坑的鐵路車站入口的擬建行人徑的大約位置
APPROXIMATE LOCATION OF PROPOSED FOOTPATH CONNECTING KWUN HOI PATH AND THE PROPOSED RAILWAY STATION ENTRANCE AT WONG CHUK HANG

接駁線 MATCH LINE
連續部分參閱圖號 SILE-G16
FOR CONTINUATION SEE DRAWING NO. SILE-G16

部分現有的巴士總站將會重置在其他地方，部分將會原址重置
PART OF THE EXISTING BUS TERMINUS TO BE REPROVISIONED AT OTHER LOCATION AND PART OF IT TO BE REPROVISIONED IN SITU
A32

現有的公共小巴總站將會原址重置
EXISTING PUBLIC LIGHT BUS TERMINUS TO BE REPROVISIONED IN SITU

建議的斜坡加固工程
PROPOSED SLOPE STABILIZATION WORKS

接駁線 MATCH LINE
連續部分參閱圖號 SILE-G08
FOR CONTINUATION SEE DRAWING NO. SILE-G08

在工程進行中及完工後將會保留、改道或修改的現有道路及行人徑
EXISTING ROADS AND FOOTPATHS TO BE MAINTAINED, DIVERTED OR MODIFIED DURING AND AFTER CONSTRUCTION
A29

香港警察學院 Hong Kong Police College

刪除擬建的通風井
PROPOSED VENTILATION SHAFTS DELETED
A30

修訂建議的斜坡加固工程範圍及方案界線
LAYOUT OF PROPOSED SLOPE STABILIZATION WORKS AND BOUNDARY OF THE SCHEME AMENDED
A19

擬建在黃竹坑的鐵路車廠的大約位置
APPROXIMATE LOCATION OF PROPOSED RAILWAY DEPOT AT WONG CHUK HANG

擬增建的通風井的大約位置
APPROXIMATE LOCATION OF PROPOSED ADDED VENTILATION SHAFT
A30

修訂擬建的通風井的布局及大約位置
LAYOUT AND APPROXIMATE LOCATION OF PROPOSED VENTILATION SHAFTS AMENDED
A30

+20.60 +18.00

0 10 20 30 40 50米 M
1 : 1000

圖例 LEGEND

- 方案界線 BOUNDARY OF THE SCHEME
- 擬建的車站及其他鐵路設施 PROPOSED STATION AND OTHER RAILWAY FACILITIES
- 擬建的車站及其他鐵路設施(地下) PROPOSED STATION AND OTHER RAILWAY FACILITIES (UNDERGROUND)
- 擬採用鑽挖或放炮或爆破的鐵路設施或隧道(地下) PROPOSED RAILWAY FACILITIES/TUNNEL BY BORED / MINED / DRILL AND BLAST METHOD (UNDERGROUND)
- 擬採用明挖回填法興建的鐵路設施或隧道(地下) PROPOSED RAILWAY FACILITIES/TUNNEL BY CUT-AND-COVER METHOD (UNDERGROUND)
- 可能永久封閉的道路（包括行車道和行人徑） ROADS (INCLUDING CARRIAGEWAY AND FOOTPATH) WHICH MAY BE CLOSED PERMANENTLY
- 擬建的鐵路高架橋 PROPOSED RAILWAY VIADUCT
- 現有的行人天橋將受影響 EXISTING FOOTBRIDGE TO BE AFFECTED
- 擬建的臨時行人天橋/地面行人過路處 PROPOSED TEMPORARY FOOTBRIDGE / AT-GRADE PEDESTRIAN CROSSING
- 擬建的行人天橋 PROPOSED FOOTBRIDGE
- 可能在其上進行填海工程或其他工程的政府前灘或海床 GOVERNMENT FORESHORE OR SEABED OVER OR UPON WHICH RECLAMATION OR OTHER WORKS MAY BE CARRIED OUT
- 現有的車站及其他鐵路設施 EXISTING STATION AND OTHER RAILWAY FACILITIES
- 擬建的臨時架空輸送帶系統 PROPOSED TEMPORARY OVERHEAD CONVEYANCE SYSTEM
- 擬建的鐵路隧道入口 PROPOSED RAILWAY TUNNEL APPROACH
- +18.0 以主水平基準為依據之擬建路軌大約水平(米) PROPOSED APPROXIMATE TRACK LEVEL IN m P.D.
- 1 圖則修改 DRAWING REVISION
- A1 修訂參考編號(參考憲報公告) AMENDMENT REFERENCE NUMBER (SEE GAZETTE NOTICE)
- 修訂範圍 AMENDMENT AREA

一般說明 GENERAL NOTES

1. 有關一般說明參閱圖號 SILE - G01.
   FOR GENERAL NOTES, REFER TO DRAWING NO. SILE - G01.

修訂表 TABLE OF AMENDMENTS

修改 REV	日期 DATE	繪圖 BY	核對 SUB	角責 APP	說明 DESCRIPTION

SIGNED 袁浚國 YUEN WOO KOK, ANTHONY

獲准發出 APPROVED FOR ISSUE

15/3/2018 發出日期 DATE OF ISSUE

路政署 鐵工程師/鐵路拓展 1 - 3
CHIEF ENGINEER/ RAILWAY DEVELOPMENT 1-3
HIGHWAYS DEPARTMENT

圖則名稱 DRAWING TITLE

鐵路條例(第519章)
南港島線(東段)
暫時封閉警校道、香葉道和南朗山道路段

RAILWAYS ORDINANCE (CHAPTER 519)
SOUTH ISLAND LINE (EAST)
TEMPORARY CLOSURE OF SECTIONS OF POLICE SCHOOL ROAD, HEUNG YIP ROAD AND NAM LONG SHAN ROAD

圖號 DRAWING NO. SILE/G09/0003/10

比例 SCALE 1:1000 (A1) 或如圖示 OR AS SHOWN

香港特別行政區政府
THE GOVERNMENT OF THE HONG KONG SPECIAL ADMINISTRATIVE REGION
路政署 HIGHWAYS DEPARTMENT
鐵路拓展處 RAILWAY DEVELOPMENT OFFICE

香葉道 HEUNG YIP ROAD
擬建的鐵路高架橋 PROPOSED RAILWAY VIADUCT
擬建的箱形暗渠 PROPOSED BOX CULVERTS
地面水平 GROUND LEVEL
切面圖 不按比例 SECTION U NOT TO SCALE

黃竹坑道 WONG CHUK HANG ROAD
現有的高架道路 EXISTING ELEVATED ROAD
業勤街 YIP KAN STREET
擬建的鐵路高架橋 PROPOSED RAILWAY VIADUCT
在工程進行中及完工後將會修改或封閉部分現有位於天台的休憩處 PART OF EXISTING SITTING-OUT AREA AT ROOF TOP TO BE MODIFIED OR CLOSED DURING AND AFTER CONSTRUCTION
南朗山道熟食市場 NAM LONG SHAN ROAD COOKED FOOD MARKET
擬建的箱形暗渠 PROPOSED BOX CULVERTS
南朗山道休憩處 NAM LONG SHAN ROAD SITTING-OUT AREA
擬建的升降機、樓梯及行人天橋的大約位置 APPROXIMATE LOCATION OF PROPOSED LIFTS, STAIRS AND FOOTBRIDGE
方案界線 BOUNDARY OF THE SCHEME
切面圖 不按比例 SECTION T NOT TO SCALE

PLOT DRV: E:\tb\Plot\V8\v8_printer.plt 19/03/2018 08:25:14
PRINTED BY: fkko
FILENAME: X:\Land\SL\PLOT\Drawing\road closure\rev\VER JSIGNED\WEB\SILE-G09-0003-10.dgn